

Proposal



Brams Construction

Harrison Brams
1358 Telfair Drive
Jupiter Fl 33458
U.S.A

Bill To:

Jupiter Lakes HOA
431 Jupiter Lakes Blvd.
Jupiter FL
U.S.A

Date : Jul 23, 2025

#	Item Description	Qty	Rate		Amount
1	Remove and replace Cracked, Sunken and lifted sidewalk in a minimum of 4 ft sections. Pricing for 3000 PSI Concrete with Fiber mesh. 600 Square Foot total.	1	20000	0.00 0	20000.00

Sub Total 20000.00

TOTAL \$20,000.00

Scope Of Work

Saw cut all damaged sections, remove and dispose. Form Pour and Finish 600 linear feet of 3 foot sidewalk. Concrete will be placed ensuring proper grade, pitch for drainage and even transitions.